IMPORTANT PRODUCT INFORMATION

GFK-2965M Jun 2022

PACSystems[™] RSTi-EP

PROFINET[®] SCANNER (EPXPNS001)





Warnings and Caution Notes as Used in this Publication

WARNING

Warning notices are used in this publication to emphasize that hazardous voltages, currents, temperatures, or other conditions that could cause personal injury exist in this equipment or may be associated with its use.

In situations where inattention could cause either personal injury or damage to equipment, a Warning notice is used.

ACAUTION

Caution notices are used where equipment might be damaged if care is not taken.

Note: Notes merely call attention to information that is especially significant to understanding and operating the equipment.

These instructions do not purport to cover all details or variations in equipment, nor to provide for every possible contingency to be met during installation, operation, and maintenance. The information is supplied for informational purposes only, and Emerson makes no warranty as to the accuracy of the information included herein. Changes, modifications, and/or improvements to equipment and specifications are made periodically and these changes may or may not be reflected herein. It is understood that Emerson may make changes, modifications, or improvements to the equipment referenced herein or to the document itself at any time. This document is intended for trained personnel familiar with the Emerson products referenced herein.

Emerson may have patents or pending patent applications covering subject matter in this document. The furnishing of this document does not provide any license whatsoever to any of these patents.

Emerson provides the following document and the information included therein as-is and without warranty of any kind, expressed or implied, including but not limited to any implied statutory warranty of merchantability or fitness for particular purpose.

Product Description

The EPXPNS001 PROFINET Scanner is a PROFINET I/O device certified by the PROFINET user organization. The network adapter is the head module for the RSTi-EP system bus, to which up to 64 active RSTi-EP modules can be connected. The PROFINET network adapter has two Ethernet ports and an integrated switch.

The PROFINET Scanner can be accessed with a system-independent web server application via the USB service interface or the Ethernet. Thus, all information, such as diagnostics, status values, and parameters, can be read and all connected modules can be simulated or forced.

The station's main power supply is integrated with the PROFINET Scanner. Power is supplied via two 4-pole connectors, separated into the input and output current paths.

Caution, the RSTi-EP station is usually installed on a horizontally positioned DIN rail. Installation on vertically positioned DIN rails is also possible. However, the heat dissipation is reduced such that the derating values change (refer to the section, Thermal Derating).

Modules should be allowed to de-energize for a minimum of 10 seconds after powering down, before starting any maintenance activity. The PROFINET Scanner cannot be hot-swapped.

Refer to the RSTi-EP Slice I/O User Manual (GFK-2958) for additional information.

Refer to the RSTi-EP Power Supply Reference Guide, a software utility available on PAC Machine Edition(PME) V9.00, for detailed power-feed requirements.

Module Features

- Supports up to 64 active RSTi-EP modules
- Spring-style technology for ease of wiring
- DIN rail mounted
- Double-click installation for positive indication of correct installation
- Built-in Web Server for diagnostic information and firmware update through Ethernet and micro USB port
- Supports Media Redundancy Protocol (MRP) Client mode operation
- Support for daisy-chain/line, star, or ring (MRP) technologies
- Two switched Ethernet ports; 8-conductor RJ-45 shielded twisted pair 10/100 Mbps copper interfaces
- Fast start-up < 500 ms with a maximum of 10 modules

Ordering Information

Module	Description			
EPXPNS001	RSTi-EP Slice I/O PROFINET IRT Network Adapter			

Specifications

Specifications	EPXPNS001					
System data						
Connection		2 x RJ-45				
Fieldbus protocol	PROFINET V	/ersion 2.3 Class C I/O Device (IRT, RT)				
	Input data width	max. 512 bytes				
	Output data width	max. 512 bytes				
Process image	Parameter data	max. 4362 bytes				
	Diagnostic data	max. 1408 bytes				
Number of modules		max. 64 active				
Configuration interface		Micro USB 2.0				
	Fieldbus	Max. 100 Mbps				
Transfer rate	RSTi-EP system bus	Max. 48 Mbps				
Data format	Default: Motorola	Configurable: Intel				
		Ims, 2ms, 4ms, 8ms, 16ms, 32ms, 64ms, 128ms,				
PROFINET I/O Update Rate	256ms, and 512ms	11115, 21115, 41115, 61115, 101115, 521115, 041115, 1261115,				
Supports MRP		Yes * [Minimum I/O Update Rate for bumpless operation in an MRP ring topology is 32ms and slower for EPXPNS001]				
Supply						
Supply voltage for system and inputs		20.4V – 28.8V				
Supply voltage for outputs	20.4V – 28.8V					
Max. feed-in current for input modules		10 A				
Max. feed-in current for output modules	10 A					
Current consumption from system current path I _{SYS}	116 mA					
Connection data						
Type of connection		Spring style				
Conductor cross-section	Single-wired, fine-wired	0.14 – 1.5 mm² (AWG 26 – 16)				
General data	-					
Operating temperature	-20	0°C to +60°C (-4 °F to +140 °F)				
Storage temperature	-40	°C to +85°C (-40 °F to +185 °F)				
Air humidity (operation/transport)	5% to 95%, noncondensing as per DIN EN 61131-2					
Width		52 mm (2.05 in)				
Depth	76 mm (2.99 in)					
Height	120 mm (4.72 in)					
Weight		220 g (7.76 oz)				
Configuration	V2.3 GSDML file is available on the Support website <u>https://www.emerson.com/Industrial-Automation-Controls/support</u> for download and import into PAC Machine Edition. The GSDML supporting a firmware release is part of the firmware upgrade kit available on the Support website.					

LEDs

LED Status Indicators

LED	Indication	LED State/Description				
PWR	Power LED	Green: Supply voltage connected				
		Red: Configuration error, or error in the PROFINET Scanner, or error in a module, or				
SF	System fault	there is a new diagnostic report				
		Red flashing: Station in Force mode				
		Red: No connection to the Fieldbus				
BF	Bus fault	Red flashing: Configuration error, no connection to the control unit, or error in the				
		parameter set				
МТ	Maintenance	′ellow: Error on the system bus or Fieldbus				
Required		Tellow. Error on the system bus of heldbus				
LINK 1	Connection	Green: Connection established between port 1 of the PROFINET Scanner and				
	Connection	another field device				
ACT 1	Active	Yellow flashing: Data being exchanged on port 1				
LINK 2	Connection	Green: Connection established between port 2 of the PROFINET Scanner and				
	Connection	another field device				
ACT 2	Active	Yellow flashing: Data being exchanged on port 2				


LED Indicators

	LED	EPXPNS101
	Power	Green: Supply voltage > 18 V DC
× 1	Supply	Red: At least one current path < 18 V
PWR SF		
x 2 x 2 x 2 x 2 x 2 x 2 x 2 x 2		
EPXPNS101 MAC-Address: Service		
00-15-7E-11-73-9D X 3	3.1	Green: Input current path supply voltage > 18 V DC
	3.2	Red: Input current path supply voltage < 18 V DC
	3.3	
	3.4	Red: Internal fuse defective
	4.1	Green: Output current path supply voltage > 18 V DC
	4.2	Red: Output current path supply voltage < 18 V DC
	4.3	
	4.4	Red: Internal fuse defective

Field Wiring

The connection frame has one connector, and two 24 V DC wires can be connected to each connector, along with two ground connections. Those four connectors are used as shown in the following figure. The Spring style technology allows either finely stranded or solid wire with crimped wire-end ferrules or ultrasonically welded wires, each with a maximum cross-section of 1.5 mm² (16 gauge), to be inserted easily through the opening in the clamping terminal without having to use tools. To insert fine stranded wires without wire-end ferrules, the pusher must be pressed in with a screwdriver and released to latch the wire.

Figure 1: Connector Block



Connector Specifications:


- Conductor cross-section 0.14 to 1.5 mm² (26 16 guage)
- Maximum ampacity: 10 A
- 4-pole

The modules do not have a fused sensor/activator power supply. All cables to the connected sensors/actuators must be fused corresponding to their conductor cross-sections (as per Standard DIN EN 60204-1, section 12).

Refer to the RSTi-EP Slice I/O User Manual (GFK-2958) for additional information.


For technical assistance, go to https://www.emerson.com/Industrial-Automation-Controls/support

Figure 2: EPXPNS001



Connection Block Diagrams

Figure 3: EPXPNS001



Installation in Hazardous Areas

WARNING

- EQUIPMENT LABELED WITH REFERENCE TO CLASS I, GROUPS A, B, C & D, DIV. 2 HAZARDOUS AREAS IS SUITABLE FOR USE IN CLASS I, DIVISION 2, GROUPS A, B, C, D OR NON-HAZARDOUS AREAS ONLY
- EXPLOSION HAZARD SUBSTITUTION OF COMPONENTS MAY IMPAIR SUITABILITY FOR CLASS I, DIVISION 2;
- EXPLOSION HAZARD WHEN IN HAZARDOUS AREAS, TURN OFF POWER BEFORE REPLACING OR WIRING MODULES; AND
- EXPLOSION HAZARD DO NOT CONNECT OR DISCONNECT EQUIPMENT UNLESS POWER HAS BEEN SWITCHED OFF OR THE AREA IS KNOWN TO BE NONHAZARDOUS.

ATEX Marking

II 3 G Ex Na IIC T4 Gc
 Ta: -20°C to +60°C (-4° F to +140 °F)

Thermal Derating

The power supply is restricted according to the temperature. The following values apply for the horizontal and vertical positioning of the RSTi-EP station:

Temperature-dependent Values for the Power Supply

Power Supply	Horizontal	Vertical
Network adapter power supply	60°C (140 °F) : 2 x 8 A	55°C (131 °F) : 2 x 6 A
	55°C (131 °F) : 2 x 10 A	50°C (122 °F) : 2 x 8 A
Power-feed module power supply	60°C (140 °F) : 1 x 10 A	55°C (131 °F) : 1 x 8 A

Refer to the RSTi-EP Slice I/O Module User Manual (GFK-2958) for additional information.

Supported Modules and Power Supplies

The following modules can be used with this release of the RSTI-EP PROFINET Network Adapter :

Catalog Number	Module Description					
Digital Input Modules						
EP-1214	Digital Input, 4 Points, Positive Logic 24VDC, 2,3, or 4 Wire					
EP-1218	Digital Input, 8 Points, Positive Logic, 24VDC 2 Wire					
EP-1318	Digital Input, 8 Points, Positive Logic, 24VDC 3 Wire					
EP-125F	Digital Input, 16 Points, Positive Logic, 24VDC, 1 Wire					
EP-153F	Digital Input, 16 Points, Negative Logic, 24VDC, 1 Wire					
EP-12F4	Digital Input, 4 Points, Positive Logic 24VDC, 2,3, or 4 Wire, Timestamp					
EP-1804	Digital Input, 4 Points 110/230 VAC (65 – 277 VAC), 2 Wire, Isolated					
Digital Output Modules						
EP-2214	Digital Output, 4 Points, Positive Logic 24VDC, 0.5A, 2,3, or 4 Wire					
EP-2614	Digital Output, 4 Points, Positive Logic 24VDC, 2.0A, 2,3, or 4 Wire					
EP-2634	Digital Output, 4 Points, Positive/Negative Logic 24VDC, 2.0A, 2,3, or 4 Wire					
EP-2218	Digital Output, 8 Points, Positive Logic, 24VDC, 0.5A, 2 Wire					
EP-225F	Digital Output, 16 Points, Positive Logic, 24VDC, 0.5A, 1 Wire					
EP-291F	Digital Output, 16 Points, Negative Logic, 24VDC, 0.5A, 1 Wire					
Digital Relay Output Mod	lules					
EP-2714	Digital Relay Output, 4 Points, Positive Logic, 24 - 220 VDC/VAC, 6A, 2 Wire					
EP-2814	Solid-state Relay Output Module					
Analog Input Modules						
EP-3164	Analog Input, 4 Channels Voltage/Current 16 Bits 2, 3, or 4 Wire					
EP-3264	Analog Input, 4 Channels Voltage/Current 16 Bits with Diagnostics 2, 3, or 4 Wire					
EP-3124	Analog Input, 4 Channels Voltage/Current 12 Bits 2, 3, or 4 Wire					
EP-3368	Analog Input, 8 Channels Current 16 Bits 2, 3, or 4 Wire					
EP-3468	Analog Input, 8 Channels Current 16 Bits 2, 3, or 4 Wire, Channel Diagnostic					
EP-3704	Analog Input, 4 Channels RTD 16 Bits with Diagnostics 2, 3, or 4 Wire					

Catalog Number	Module Description						
EP-3804	Analog Input, 4 Channels TC 16 Bits with Diagnostics 2, 3, or 4 Wire						
EP-1813	Power Measurement Module, 8 Channels						
Analog Output Modules							
EP-4164	Analog Output, 4 Channels Voltage/Current 16 Bits 2, 3, or 4 Wire						
EP-4264	Analog Output, 4 Channels Voltage/Current 16 Bits with Diagnostics 2, 3, or 4 Wire						
Speciality Modules							
EP-5111	1 Channel High Speed Counter, AB 100 kHz 1 DO 24VDC, 0.5A						
EP-5112	2 Channel High Speed Counter, AB 100 kHz						
EP-5212	2 Channel Frequency Measurement, 100 kHz						
EP-5261	1 Channel Serial Communications, 232, 422, 485						
EP-5311	1 Channel SSI Encoder, BCD or Gray-Code Format, 5/24 VDC						
EP-5422	2 Channels PWM Output, Positive Logic, 24VDC, 2.0 A						
EP-5442	2 Channels PWM Output, Positive Logic, 24VDC, 0.5 A						
EP-5324	IO-Link Communication Module, 4 Channels						
Power Feed Modules for Input Current Path							
EP-7631	Power Module, 1 Channel 24VDC Input Flow 10A						
Power Feed Modules for Output Current Path							
EP-7641	Power Module, 1 Channel 24VDC Output Flow 10A						
Safe Feed-input Modules							
EP-1901	1 Safe Feed-Input, 24 VDC						
EP-1902	2 Safe Feed-Inputs, 24 VDC, Programmable Delay						
EP-1922	2 Safe Feed-Inputs, 24 VDC						
Potential Distribution Modules							
EP-711F	Power Module, 16 Channels 24VDC Potential Distribution +24 VDC from Input Current Path						
EP-751F	Power Module, 16 Channels 24VDC Potential Distribution +24 VDC from Output Current Path						
EP-700F	Power Module, 16 Channels 24VDC Potential Distribution Functional Earth						
EP-710F	Power Module, 16 Channels 24VDC Potential Distribution +0VDC from Input Current Path						
EP-750F	Power Module, 16 Channels 24VDC Potential Distribution +0VDC from Output Current Path						

Release History

Catalog Number	Hardwar e Version	Firmware Version	Date	Comments
EPXPNS001-ADAJ	02.00.00	02.06.02	June 22	Firmware release 02.06.02
EPXPNS001-ADAH EPXPNS001-ADAH	02.00.00	02.05.03	Dec 21 Nov 20	 Release of Firmware modified with increased startup timeout to support IO-link devices having longer startup times Release of FW file with integrated FSBL image for
		FSBL: 01.08.00		 EPXPNS001. Error fixes-"Valid module substitution" fault on EPXPNS001 - when the node is downloaded to the controller.
EPXPNS001-ADAG	02.00.00	02.04.02 FSBL: 01.08.00	Mar 20	EPXPNS001 is released with HW version 02.00.00 & with FW 02.04.02, the same as EPXPNS101.
EPXPNS001-ACAF	01.05.00	02.03.01	Dec 19	Support for two newly introduced IO modules EP-1813 (Power Measurement module) and EP-5324 (IO-Link Communication Module) with only IPI update.
EPXPNS001-ACAF	01.05.00	02.03.01	Dec 19	Firmware corrected for the display of appropriate Device Type for EPXPNS001 for "Explore Profinet" and "Profinet DCP" Tools in Machine Edition.
EPXPNS001-ACAE	01.05.00	02.03.00	Sep 19	 Following Emerson's acquisition of this product, changes have been made to apply appropriate branding and registration of the product with required certification agencies. No changes to the material, process, form, fit, or functionality. Support for new Negative logic Digital Input module(EP-153F) & Digital Output Module (EP-291F) Updates to webserver Ordering data is removed from General information section of Emerson branded products. Brand labeling of Web Application to EMERSON.
EPXPNS001-ABAD	01.05.00	02.02.00	Mar 18	 The product revision is updated to be usable in marine/shipbuilding applications and pass marine certification tests. [DNV-GL & Lloyd's Register] Enhancements and updates to Web Application : Reset button appears automatically when changes in parameter settings require a restart to take effect Added display of slot numbers to list of compatible modules after selecting a firmware file in multi-update view. Added password policy and weak password check - default username and password will remain the same. New languages for Web Server available [Korean, French, Spanish, Portuguese and Italian] Support for EP-3664 Fixed issue that live module unplug/replug sometimes corrupts I/O mapping Fixed issue that re-installation attempt of language files sometimes causes an error message
EPXPNS001-AAAC	01.04.00	02.01.00	Nov 17	Enhancements and updates to Web Application - Web Application: a. Added Tooltips for Coupler LEDs

Catalog Number	Hardwar e Version	Firmware Version	Date	Comments
				 b. Improved arrangement of module parameters & general information c. Display of raw process data next to physical value d. Web application performance improved "Disappearing" Diagnosis is not sent via Fieldbus when the module in front is pulled New parameter to group the power supply error, filter return of submodule alarms Filter diagnosis messages for bus error on hot plug
EPXPNS001-AAAB	01.04.00	01.00.04	Sep 16	 Support for three new modules, EP-1804, EP-5261, and EP-5311 Resolves a problem, see section <i>Problems Resolved by this Release</i> for more information
EPXPNS001-AAAA	01.04.00	01.00.04	Dec 15	Documentation update only added known issues
EPXPNS001-AAAA	01.04.00	01.00.04	Nov 15	Initial Release

Important Product Information for this Release

Updates

EPXPNS001-ADAJ default factory image will be 02.06.02.

The product may be upgraded in the field using the Web firmware upgrade kit, which can be downloaded from https://www.emerson.com/Industrial-Automation-Controls/support.

Module	Firmware Version	Upgrade Kit & GSDML File
EPXPNS001-ADAJ	FW - 02.06.02	 EPXPNS001-0007675-02_06_02-7.zip which includes the following files:- a. EPXPNSx01-0007675-02_06_02-7.bsc b. GSDML-V2.3-IntelligentPlatforms-EPXPNS001-20220211.xml c. IPI-GFK-2965M d. FW Upgrade Procedure

Functional Compatibility

				FW Inde	x [Ver]					
HW Index [Ver]	AA [01.00.00]	AB [02.00.00]	AC [02.01.00]	AD [02.02.00]	AE [02.03.00]	AF [02.03.01]	AG [02.04.02]	AH [02.05.01]	AH [02.05.03]	AJ [02.06.02]
AA [01.04.00]	ОК	ОК	ОК	ОК	ОК	ОК	NO	NO	NO	NO
AB [01.05.00]	NO	NO	NO	ОК	ОК	ОК	NO	NO	NO	NO
AC [01.05.00]	NO	NO	NO	ОК	ОК	ОК	NO	NO	NO	NO
AD[02.00.0 0]	NO	NO	NO	NO	NO	NO	ОК	ОК	ОК	ОК

Problems Resolved by this Release

Maintenance release

New Features and Enhancements

None

Known Restrictions and Open Issues

Subject	Description
Channel diagnostics faults are reported during hot-swapping of the modules	During hot-swap of an I/O module, the network adapter may report additional channel diagnostics messages in addition to the expected <i>Loss of Module</i> or <i>Addition of Module</i> fault
Behavior during hot removal when similar modules are configured consecutively	Where similar modules are configured consecutively in the remote I/O node, a shift in input data occurs when one of the consecutive modules is removed from the node. For example, when there are 6 RTD modules EP-3704, configured consecutively in the node, slots 1 - 6, on hot-removal of the module from slot 4, data from modules 5 and 6 would be reflected on variables configured for slots 4 and 5, respectively, with <i>Loss of Module</i> reported for slot 6.

Operational Notes

Subject	Description
Output behavior during hot- swapping	During hot insertion or removal of IO modules, a transient Loss of Power up to 500 ms may occur on the network adapter and IO modules, during which all of the outputs may drop to zero. This system behavior should be verified against the application requirements before hot insertion or removal of the IO module is done.

Product Documentation

RSTi-EP Slice I/O Module User Manual (GFK-2958) RSTi-EP Slice I/O Functional Safety Module User Manual (GFK-2956)

General Contact Information

Home link:	http://www.emerson.com/industrial-automation-controls
Knowledge Base:	https://www.emerson.com/industrial-automation-controls/support

Technical Support

Americas Phone:	1-888-565-4155 1-434-214-8532 (If toll-free option is unavailable)
	Customer Care (Quotes/Orders/Returns): <u>customercare.mas@emerson.com</u> Technical Support: <u>support.mas@emerson.com</u>
Europe Phone:	+800-4444-8001 +420-225-379-328 (If toll-free option is unavailable) +39-0362-228-5555 (from Italy - if toll-free 800 option is unavailable or dialing from a mobile telephone)
	Customer Care (Quotes/Orders/Returns): <u>customercare.emea.mas@emerson.com</u> Technical Support: <u>support.mas.emea@emerson.com</u>
Asia Phone:	+86-400-842-8599 +65-6955-9413 (All other Countries)
	Customer Care (Quotes/Orders/Returns): <u>customercare.cn.mas@emerson.com</u> Technical Support: <u>support.mas.apac@emerson.com</u>

Any escalation request should be sent to: mas.sfdcescalation@emerson.com

Note: If the product is purchased through an Authorized Channel Partner, please contact the seller directly for any support.

Emerson reserves the right to modify or improve the designs or specifications of the products mentioned in this manual at any time without notice. Emerson does not assume responsibility for the selection, use, or maintenance of any product. Responsibility for proper selection, use, and maintenance of any Emerson product remains solely with the purchaser.

© 2022 Emerson. All rights reserved.

Emerson Terms and Conditions of Sale are available upon request. The Emerson logo is a trademark and service mark of Emerson Electric Co. All other marks are the property of their respective owners.

